County Commissioners Office
Auglaize County, Ohio
February 26, 2015

NO. **1S - 099**

IN THE MATTER OF ACCEPTING THE QUOTE FROM WELLMAN BROTHERS INC FOR THE SOLARIUM LEAKS PROJECT AT THE AUGLAIZE COUNTY ADMINISTRATION BUILDING; AND AUTHORIZING EXECUTION OF QUOTE.

****

The Board of County Commissioners of Auglaize County, Ohio met in regular session on the 26th day of February, 2015.

Commissioner _Bergman_ moved the adoption of the following:

RESOLUTION

WHEREAS, Wellman Brothers Inc has submitted a quote of $9,173.00 to furnish all labor and material for the following work on the exterior of the solarium on the Auglaize County Administration Building:

- Remove the existing counter flashing where the roof meets the brick masonry. Fabricate and install new counter flashing out of aluminum sheet metal (medium bronze .032). The new counter flashing will be recessed and tuckpointed into the masonry approximately one inch. Seal the brick masonry on with Siloxane PD.
- Paint the eifs (dryvit) surface located around the perimeter of the solarium windows. Two coats on waterproofing latex paint will be applied (conflex xl). All caulk on the outer perimeter of the eifs will be re-caulked.
- Remove the metal window sills and replace with new sills fabricated out of aluminum sheet metal (medium bronze.032). The new metal sills will be fabricated so the top side will slope away from the windows. The existing metal sills slope towards the windows.

THEREFORE BE IT RESOLVED by the Board of Commissioners of Auglaize County, Ohio does hereby approve and authorize the quote from Wellman Brothers Inc. for $9,173.00 for the above stated work on the exterior of the solarium on the Auglaize County Administration Building.

Commissioner _Regula_ seconded the Resolution and upon the roll being called, the vote resulted in the adoption of the Resolution as follows:

Adopted this
26th day of
February, 2015

BOARD OF COUNTY COMMISSIONERS
AUGLAIZE COUNTY, OHIO

_____ , Yes
Douglas A. Spencer

_____ , yes
Don Regula

_____ , yes
John N. Bergman

cc: Wellman Brothers Inc.
Maintenance Supervisor – Rick Bice